

The Project consists of the construction of stormwater drainage network at the quarters of East & West Naseem and Muazliah as well as the squares of Al Moroug, Al Masiat and Al Nakeel. The project consists of 40 km length box culvert and 126 km length pipeline with all related civil and mechanical works. The main components of the project are 2,029,170 m<sup>3</sup> excavation and backfilling works, 223,785 m<sup>3</sup> concrete for box culvert, 18,820 m<sup>3</sup> concrete for encasement of pipes, 126,311 m GRP pipe (diameter 300 mm – 1,200 mm), 1,232 nos manholes and 3,350 nos catch basins, 413,249 m<sup>2</sup> re-asphalting works, 226,000 m length traffic diversion and relocation of existing utilities.

{gallery}industrial/article\_id\_1011{/gallery}

**Client** Riyadh Municipality

**Location** Riyadh / Saudi Arabia

**Contract Date** 05 November 2013

**Completion Date** 10 May 2017

{backbutton}